

City of Napoleon, Ohio

Third Street Sanitary Sewer Improvements
(Williams Street to Meekison Street)

ADDENDUM NO. 1

October 23, 2023

Plan holders on the Third Street Sanitary Sewer Improvements (Williams Street to Meekison Street) are hereby notified of the following amendments to the Contract Documents. This Addendum is hereby made a part of the Contract Documents and shall be acknowledged by responsive Bidders within Page BF-1 of the Bid Form.


1. Refer to the Notice to Bidders:

Estimate of Cost *delete* \$680,000 and replace with \$700,000.

2. Refer to the Bid Form

Remove pages CITY-BF-2 and CITY-BF-3 and replace with pages CITY-BF-2A and CITY-BF-3A.

**THIS ADDENDUM MUST BE ATTACHED TO THE BID DOCUMENTS
AND RECEIPT ACKNOWLEDGED**


Chad E. Lulfs, P.E., P.S.
City Engineer
#E-65579



ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT	UNIT PRICE	TOTAL
ROADWAY					
1	Clearing and Grubbing	1.00	LS		
2	Concrete Curb Removal	65.00	LF		
3	Concrete Pavement and Walk Removal	50.00	SY		
4	Cold Planing (0" to 1½" Deep)	3,800.00	SY		
5	6" Stabilized Crushed Aggregate-Driveways (ODOT 411)	2.00	CY		
6	3" Asphalt Concrete Base (ODOT 301 PG64-22)	2.00	CY		
7	4½" Asphalt Concrete Base (ODOT 301 PG64-22)	75.00	CY		
8	1½" Asphalt Concrete Surface Course (ODOT 823 Type 1 Medium, PG64-22)	390.00	TON		
9	6" Plain Portland Cement Concrete Pavement with 6" Crushed Aggregate Base	30.00 150.00	SY		
10	4" Concrete Walk with 4" Stabilized Crushed Aggregate Base (ODOT 411)	20.00 70.00	SY		
11	Handicap Ramp with ADA Truncated Dome Detectable Warnings	1.00	EA		
12	Concrete Curb and Gutter (All Types)	65.00	LF		
13	Temporary Relocation and Replacement of Mailboxes	5.00	EA		
14	Temporary Removal and Replacement of Ground Mounted Sign	1.00	EA		
15	3" Topsoil Hauled and Placed	100.00	CY		
16	Fertilizer, Seeding and Mulching	1,200.00	SY		
17	Construction Layout Stakes	1.00	LS		
18	Maintaining Traffic	1.00	LS		
19	Mobilization	1.00	LS		
20	Stormwater Pollution Prevention Plan	1.00	LS		
DRAINAGE					
21	8" PVC ASTM D3034 SDR-35 Storm Sewer (Type C)	9.00	LF		
22	12" PVC ASTM D3034 SDR-35 Storm Sewer (Type B)	33.00	LF		
23	Remove Existing Catch Basin	2.00	EA		
24	2'x3' Curb Inlet including Casting and Bikesafe Grate	2.00	EA		
25	Flexible Coupling with Stainless Steel Bands (All Sizes)	2.00	EA		
SANITARY SEWER					
26	6" PVC ASTM D3034 SDR-35 Sanitary (Type B)	215.00	LF		
27	6" PVC ASTM D3034 SDR-35 Sanitary (Type C)	325.00	LF		
28	8" PVC ASTM D3034 SDR-35 Sanitary (Type B)	40.00	LF		
29	10" PVC ASTM D3034 SDR-35 Sanitary (Type B)	10.00	LF		
30	12" PVC ASTM D3034 SDR-35 Sanitary (Type B)	865.00	LF		
31	18" PVC ASTM F679 Sanitary (Type B)	1,015.00	LF		

ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT	UNIT PRICE	TOTAL
32	6" on 12" PVC Wye (Heavy Duty) or, PVC Inserta Tee	5.00	EA		
33	6" on 18" PVC Wye (Heavy Duty) or, PVC Inserta Tee	16.00	EA		
34	6" 45 Degree PVC Bend (Heavy Duty)	50.00	EA		
35	PVC Coupling (Heavy Duty) – All Sizes	2.00	EA		
36	6" Cleanout (with Inverted Cap)	19.00	EA		
37	6" Cleanout (with Brass Lid)	1.00	EA		
38	Flexible Coupling with Stainless Steel Bands (All Sizes)	30.00	EA		
39	Sanitary Sewer Abandoned and Filled with Grout (All Sizes)	25.00	CY		
40	Sanitary Manhole Removed	7.00	EA		
41	48" Diameter Sanitary Manhole with Standard Cone	7.00	EA		
42	Sanitary Manhole Casting with Gasketed Lid Marked "SANITARY SEWER"	7.00	EA		
43	Sanitary Sewer Televising	1,930.00	LF		
TOTAL:				\$	