

ERIE STREET AND WEST CLINTON STREET IMPROVEMENTS

ADDENDUM No. 1

October 8, 2026

Plan holders on the Erie Street and West Clinton Street Improvements project are hereby notified of the following amendments to the Contract Documents.

BID SCHEDULE

Delete page CITY-BF-2/Bid Schedule and replace with the attached CITY-BF-2A/Bid Schedule.

GENERAL CONDITIONS

Article 9 – Contractor Payment/Additional Quantities

Delete page CITY-GC-48 and replace with the attached CITY-GC-48A.

Article 15 – Subcontractors and Material Suppliers

Section 15.1 – City's Approval

15.1.1.1 The City reserves the right to reject any Subcontractor or Material Supplier.

Be advised the City of Napoleon, Ohio hereby rejects Henry W. Bergman, Inc., Genoa, Ohio, as a subcontractor or contractor.

**THIS ADDENDUM MUST BE ATTACHED TO THE BID DOCUMENTS
AND RECEIPT ACKNOWLEDGED**


Chad E. Lulfs, P.E., P.S.
City Engineer
#E-65579



BID SCHEDULE

ITEM NO.	DESCRIPTION	ESTIMATED QUANTITY	UNIT	UNIT PRICE	TOTAL
ROADWAY					
1	Clearing and Grubbing	1.00	LS		
2	Tree and Stump Removal (12"-24")	2.00	EA		
3	Tree and Stump Removal (24"-42")	9.00	EA		
4	Concrete Curb Removal (All Types)	975.00	LF		
5	Concrete Walk and Pavement Removal	700.00	SY		
6	Roadway and Driveway Excavation and Embankment	550.00	CY		
7	Roadway Excavation – Undercutting Contingency	55.00	CY		
8	Pavement Planing, Asphalt	4,400.00	SY		
9	Tack Coat (West Clinton Street)	230.00	GAL		
10	Subgrade Compaction	1,200.00	SY		
11	Subgrade Stabilization Fabric	1,200.00	SY		
12	8" Aggregate Base (ODOT 304 – 2 Lifts)	250.00	CY		
13	12" Aggregate Base (ODOT 304 – 2 Lifts)				
	Undercutting Contingency	60.00	CY		
14	3" Asphalt Concrete Base (ODOT 301 PG64-22) (449)	~~80.00~~ 5.00	CY		
14A	4½" Asphalt Concrete Base (ODOT 301 PG64-22) (449)	130.00	CY		
15	1½" Asphalt Concrete Intermediate Course (ODOT 823 Type 2 Light, PG64-22) (449)	40.00	CY		
16	¾" Asphalt Concrete Intermediate Scratch Course (ODOT 823 Type 2 Light, PG64-22) (449) (West Clinton Street)	200.00	TON		
17	1½" Asphalt Concrete Surface Course, ODOT 823 Type 1 Light (449) PG64-22	40.00	CY		
18	1½" Asphalt Concrete Surface Course, ODOT 823 Type 1 Light, (449) PG64-22 (West Clinton Street)	400.00	TON		
19	6" Plain Portland Cement Concrete Pavement with 6" Crushed Aggregate Base (ODOT 304)	250.00	SY		
20	4" Concrete Walk (with 4" Stabilized Crushed Aggregate ODOT 411)	3,200.00	SF		
21	6" Concrete Walk (with 6" Stabilized Crushed Aggregate ODOT 411)	200.00	SF		
22	Handicap Ramp with ADA Truncated Dome Detectable Warnings	9.00	EA		
23	Type 2 Concrete Curb	800.00	LF		
24	Type 6 Concrete Curb	190.00	LF		
25	6" Corrugated Polyethylene Tubing with Filter Sock (including All Fittings and No. 8 Stone Fill)	800.00	LF		
26	Removal of Ground Mounted Sign and Re-erect	3.00	EA		
27	3" Topsoil	100.00	CY		
28	Fertilizer, Seeding and Mulching	1,100.00	SY		
29	Construction Layout Stakes	1.00	LS		
30	Maintaining Traffic	1.00	LS		
31	Mobilization	1.00	LS		
32	Stormwater Pollution Prevention	1.00	LS		
ROADWAY SUBTOTAL:					\$

under that particular item, but also all costs for doing related Work as set forth in these Specifications and/or on the Contract Drawings or implied in carrying out their intent. No claim will be accepted from the Contractor for not using any item or for increasing or decreasing quantities on any item.

Additional quantities have been added to the calculated quantities of some of the bid items. No claim will be accepted from the Contractor for not using the extra quantities or for increasing or decreasing them.

The bid items along with the approximate extra quantities are as follows:

<i>Item No.</i>	<i>Description</i>	<i>Unit</i>	<i>Extra Quantity</i>
ROADWAY			
4	Concrete Curb Removal (All Types)	LF	25.00
5	Concrete Walk and Pavement Removal	SY	28.00
6	Roadway and Driveway Excavation and Embankment	CY	28.00
7	Roadway Excavation – Undercutting Contingency	CY	3.00
8	Pavement Planing, Asphalt	SY	106.00
9	Tack Coat (West Clinton Street)	GAL	5.00
10	Subgrade Compaction	SY	93.00
11	Subgrade Stabilization Fabric	SY	93.00
12	8" Aggregate Base (ODOT 304 – 2 Lifts)	CY	27.00
13	12" Aggregate Base (ODOT 304 – 2 Lifts) Undercutting Contingency	CY	8.00
14	3" Asphalt Concrete Base (ODOT 301 PG64-22) (449)	CY	~~8.00~~ 4.00
14A	4½" Asphalt Concrete Base (ODOT 301 PG64-22) (449)	CY	8.00
15	1½" Asphalt Concrete Intermediate Course (ODOT 823 Type 2 Light, PG64-22) (449)	CY	4.00
16	¾" Asphalt Concrete Intermediate Scratch Course (ODOT 823 Type 2 Light, PG64-22) (West Clinton Street)	TON	12.00
17	1½" Asphalt Concrete Surface Course, ODOT 823 Type 1 Light, (449) PG64-22	CY	4.00
18	1½" Asphalt Concrete Surface Course, ODOT 823 Type 1 Light, (449) PG64-22 (West Clinton Street)	TON	24.00
19	6" Plain Portland Cement Concrete Pavement with 6" Crushed Aggregate Base (ODOT 304)	SY	14.00
20	4" Concrete Walk with 4" Stabilized Crushed Aggregate (ODOT 411)	SF	129.00
21	6" Concrete Walk with 6" Stabilized Crushed Aggregate (ODOT 411)	SF	20.00
23	Type 2 Concrete Curb	LF	30.00
24	Type 6 Concrete Curb	LF	10.00
25	6" Corrugated Polyethylene Tubing with Filter Sock (including All Fittings and No. 8 Stone Fill)	LF	30.00
27	3" Topsoil	CY	8.00
28	Fertilizer, Seeding and Mulching	SY	90.00