

## **ERIE STREET AND WEST CLINTON STREET IMPROVEMENTS**

---

### **ADDENDUM No. 2**

---

October 13, 2026

Plan holders on the Erie Street and West Clinton Street Improvements project are hereby notified of the following amendments to the Contract Documents.

#### **NOTICE TO BIDDERS**

Sealed Bids will be received by the City of Napoleon at the office of the Finance Director at 255 West Riverview Avenue, Napoleon, Ohio until 11:00 a.m. on ~~Wednesday~~, **MONDAY, OCTOBER 14, OCTOBER 19, 2026**. The bids will be opened and read publicly immediately thereafter for furnishing all labor, materials and equipment necessary to complete the project known as **Erie Street and West Clinton Street Improvements** in accordance with the Drawings and Specifications furnished by the Architect/Engineer.

#### **BID SCHEDULE**

Delete page CITY-BF-2A/Bid Schedule and replace with the attached CITY-BF-2A/Bid Schedule.

**THIS ADDENDUM MUST BE ATTACHED TO THE BID DOCUMENTS  
AND RECEIPT ACKNOWLEDGED**

  
Chad E. Lulfs, P.E., P.S.  
City Engineer  
#E-65579



# BID SCHEDULE

| ITEM                     |                                                                                                              | ESTIMATED |      | UNIT  |           |
|--------------------------|--------------------------------------------------------------------------------------------------------------|-----------|------|-------|-----------|
| NO.                      | DESCRIPTION                                                                                                  | QUANTITY  | UNIT | PRICE | TOTAL     |
| <b>ROADWAY</b>           |                                                                                                              |           |      |       |           |
| 1                        | Clearing and Grubbing                                                                                        | 1.00      | LS   |       |           |
| 2                        | Tree and Stump Removal (12"-24")                                                                             | 2.00      | EA   |       |           |
| 3                        | Tree and Stump Removal (24"-42")                                                                             | 9.00      | EA   |       |           |
| 4                        | Concrete Curb Removal (All Types)                                                                            | 975.00    | LF   |       |           |
| 5                        | Concrete Walk and Pavement Removal                                                                           | 700.00    | SY   |       |           |
| 6                        | Roadway and Driveway Excavation and Embankment                                                               | 550.00    | CY   |       |           |
| 7                        | Roadway Excavation – Undercutting Contingency                                                                | 55.00     | CY   |       |           |
| 8                        | Pavement Planing, Asphalt                                                                                    | 4,400.00  | SY   |       |           |
| 9                        | Tack Coat (West Clinton Street)                                                                              | 230.00    | GAL  |       |           |
| 10                       | Subgrade Compaction                                                                                          | 1,200.00  | SY   |       |           |
| 11                       | Subgrade Stabilization Fabric                                                                                | 1,200.00  | SY   |       |           |
| 12                       | 8" Aggregate Base (ODOT 304 – 2 Lifts)                                                                       | 250.00    | CY   |       |           |
| 13                       | 12" Aggregate Base (ODOT 304 – 2 Lifts) Undercutting Contingency                                             | 60.00     | CY   |       |           |
| 14                       | 3" Asphalt Concrete Base (ODOT 301 PG64-22) (449)                                                            | 85.00     | CY   |       |           |
| 14A                      | 4½" Asphalt Concrete Base (ODOT 301 PG64-22) (449)                                                           | 130.00    | CY   |       |           |
| 15                       | 1½" Asphalt Concrete Intermediate Course (ODOT 823 Type 2 Light, PG64-22) (449)                              | 40.00     | CY   |       |           |
| 16                       | ¾" Asphalt Concrete Intermediate Scratch Course (ODOT 823 Type 2 Light, PG64-22) (449) (West Clinton Street) | 200.00    | TON  |       |           |
| 17                       | 1½" Asphalt Concrete Surface Course, ODOT 823 Type 1 Light (449) PG64-22                                     | 40.00     | CY   |       |           |
| 18                       | 1½" Asphalt Concrete Surface Course, ODOT 823 Type 1 Light, (449) PG64-22 (West Clinton Street)              | 400.00    | TON  |       |           |
| 19                       | 6" Plain Portland Cement Concrete Pavement with 6" Crushed Aggregate Base (ODOT 304)                         | 250.00    | SY   |       |           |
| 20                       | 4" Concrete Walk (with 4" Stabilized Crushed Aggregate ODOT 411)                                             | 3,200.00  | SF   |       |           |
| 21                       | 6" Concrete Walk (with 6" Stabilized Crushed Aggregate ODOT 411)                                             | 200.00    | SF   |       |           |
| 22                       | Handicap Ramp with ADA Truncated Dome Detectable Warnings                                                    | 9.00      | EA   |       |           |
| 23                       | Type 2 Concrete Curb                                                                                         | 800.00    | LF   |       |           |
| 24                       | Type 6 Concrete Curb                                                                                         | 190.00    | LF   |       |           |
| 25                       | 6" Corrugated Polyethylene Tubing with Filter Sock (including All Fittings and No. 8 Stone Fill)             | 800.00    | LF   |       |           |
| 26                       | Removal of Ground Mounted Sign and Re-erect                                                                  | 3.00      | EA   |       |           |
| 27                       | 3" Topsoil                                                                                                   | 100.00    | CY   |       |           |
| 28                       | Fertilizer, Seeding and Mulching                                                                             | 1,100.00  | SY   |       |           |
| 29                       | Construction Layout Stakes                                                                                   | 1.00      | LS   |       |           |
| 30                       | Maintaining Traffic                                                                                          | 1.00      | LS   |       |           |
| 31                       | Mobilization                                                                                                 | 1.00      | LS   |       |           |
| 32                       | Stormwater Pollution Prevention                                                                              | 1.00      | LS   |       |           |
| <b>ROADWAY SUBTOTAL:</b> |                                                                                                              |           |      |       | <b>\$</b> |